

Rig MDC82

XJ750 (ZEPC)
750HP
Workover Rig

- **Substructure**

DZ195/6.7-S, Height 6.7 M.

- **Hook Load**

1800 KN . (10 Lines).

- **Setback Load**

1100 KN

- **Mast**

JJ19540 , Height 40.2 M

- **Drawwork,**

JC30 , 750 HP &Drilling line 1 ¼"

- **Auxiliary Brake**

PZ40 Hydraulic disc brake.

EATON 324 WCB2, inner circulation.
water cooling.

- **Rig Power Supply.**

2 Engine CAT C-15 - 540 HP

- **Mud Pump Engine x Qty**

1x CAT C27 - 652 KW.

- **Travelling Equipment**

YG180, 200 Ton (10 Lines).

- **Rotary**

ZJ30CZ-04, 20 ½"

- **Well Control Equipment (SHENKAI)**

- 11 " Annular Preventer 5000 PSI.

- 11" Double Ram preventer.

- Drilling Spool: 11" – 5000 Psi.

- 11 " Annular Preventer 3000 PSI.

- 11" Ram double preventer

- Drilling Spool: 11" – 3000 Psi.

- 7 1/16 " Annular Preventer 5000 PSI.

- 7 1/16" Double Ram preventer

- Drilling Spool: 7 1/16" – 3000 Psi.

- 3 1/8" – 5000 psi Hydraulic & Manual

Choke Valves

- 3 1/8" – 5000 psi Manual Kill Valves

- **Drill String**

3 ½ " , NC-38 , G105-13.30 lb/ft. (150
Drill String)

- **Safety Equipment**

As required by regulations.